
SAN FRANCISCO UNIFIED SCHOOL DISTRICT
2011 PROPOSITION A BOND PROGRAM
Sunnyside Elementary School
Bungalow Replacement and Modernization

ADDENDUM NO. 1

PROJECT: Sunnyside Elementary School
250 Foerster Street
San Francisco 94112

DATE: 23 January 2014

DSA File No. 38-1

DSA APP. No. 01-113535

OWNER: San Francisco Unified School District
135 Van Ness Avenue
San Francisco, CA 94102

Notice is hereby given to all prospective bidders that plans and specifications on the subject project are modified as hereinafter set forth. This Addendum shall be attached to and form a part of the plans and specifications. All bidders must acknowledge receipt of this addendum on the Bid Form. In case of difference with previous addenda or communications, this addendum takes precedence.

It is the responsibility of all bidders to notify all subcontractors from whom they request bids and from whom they accept bids of all changes contained in this addendum.

PROJECT MANUAL

1. Item No. PM-1

Reference: Section 00100 – Notice to Contractors Calling for Bids

Description: Paragraph #6 – Delete the phrase:
(d) Statement of Bidder's Qualifications

2. Item No. PM-2

Reference: Section 00200 – Instructions to Bidders

Description: Paragraph #7 Documents Accompanying Bid Proposal, delete:
c: Statement of Bidder's Qualifications

3. Item No. PM-3

Reference: Section 00355 – Project Labor Agreement

Description: Article XII, Section 5 – Employment of Interns, para (b) Replace with the following:

(b) Interns shall be paid the California minimum wage. To cover intern wages, each Prime Contractor performing work under the Agreement shall contribute \$1,240 (twelve hundred forty dollars) to be deposited in a fund to be maintained by the District at a time to be determined but not prior to the Notice to Proceed. District representatives of the Facilities, College and Career Readiness, and Human Resources Departments shall determine this amount in advance of project bidding, and the Facilities Department shall

state it and the date of its payment in bid specifications for each project. The obligation of each Prime Contractor to contribute for intern wages is independent of placement of an intern in the Prime Contractor's project office and of scheduling of the Prime Contractor's work under the Agreement.

4. Item No. PM-4

Reference: Section 00400 – Bid Form
Description: Replace entire section
Attachment: Section 00400 – Bid Form (Addendum 1)

5. Item No. PM-5

Reference: Section 00480 – Project Labor Agreement – Letter of Assent
Description: Replace the entire section
Attachment: 00480 – Project Labor Agreement – Letter of Assent (Addendum 1)

6. Item No. PM-6

Reference: Section 01010 – Summary of Work
Description: Replace PART 1, item 1.7, A. Separate Contract with the following:
Interim Housing: A separate contract has been awarded to Mobile Modular for installation of two (2) interim housing classrooms and the removal of six (6) interim housing classrooms. Contractor responsible for coordination of units, including required SFMTA no parking signage.

7. Item No. PM-7

Reference: Section 01210 – Allowances
Description: Add to PART 3, item 3.3 the following:
B. ALLOWANCE NO. 2 – PHONE EQUIPMENT - \$50,000
Lump sum of \$50,000 for District phone system equipment as directed by District. All related infrastructure is included in the base bid. Work to be installed per 00800 Special Conditions and Phasing Plan.

8. ITEM NO. PM-8

Reference: Section 16720 Motion Detection Security System
Description: Replace entire section.
Attachment: Section 16720 - Motion Detection Security System (Addendum 1)

9. Item No. PM-9

Reference: Section 16723 Voice and Data Communications
Description: Replace Sections 2.14 through 2.16 with:

2.14 MDF Rack Equipment List

A. Equipment List

1. Qty. 1 Cisco WS-C2960X-48FPD-L

- 2. Qty. 3 Cisco WS-C2960X-48TD-L
- 3. Qty. 4 Cisco WS-C2960X-STACK
- 4. Qty. 4 Cisco CAB-STK-E-3M
- 5. Qty. 4 Cisco SFP-10G-SR
- 6. Qty. 300 5 ft. Blue CAT6 Snagless Patch Cable
- 7. Qty. 50 5 ft. White CAT6 Snagless Patch Cable
- 8. Qty. 4 2 Meter LC-LC OM3 (TEAL) Multimode Fiber Optic Patch Cable

2.15 IDF Wall Rack Equipment List

A. Equipment List:

- 1. Qty. 1 Cisco WS-C2960X-48FPD-L
- 2. Qty. 1 Cisco WS-C2960X-48TD-L
- 3. Qty. 2 Cisco WS-C2960X-STACK
- 4. Qty. 48 5 ft. Blue CAT6 Snagless Patch Cable
- 5. Qty. 48 5 ft. White CAT6 Snagless Patch Cable

2.16 Wireless Access Point List

A. Points List:

- 1. Qty. 22 Ruckus 901-7982-US00
- 2. Qty. 22 Ruckus 902-0100-0000
- 3. Qty. 1 Ruckus 901-7782-US51

B. Exterior Wireless Access Point to include the following::

- 1. Qty. 1 Oberon (or similar) 1026-12106 (12"x10"x6" NEMA Exterior Enclosure for Wireless AP's)
- 2. Qty. 1 Leviton D6753-00E Industrial Connector Housing, CAT6
- 3. Qty. 1 Leviton D670K-152 Industrial Outlet Kit, 2 port
- 4. Qty. 1 Leviton D6721-03E/05E Industrial Plug-to RJ45 Patch Cord
- 5. The Leviton products are used to connect the CAT6 indoor cable and convert them for outdoor use.

10. ITEM NO. PM-10

Reference: Section 16725 Assisted Listening System

Description: Replace paragraph 1.2 A1 as follows:

Portable FM type assistive listening system for Multi-Purpose Room as manufactured by Williams Sound Corporation complete with all required transmitters, receivers, earphone and accessories. All electrical components shall be listed and approved by Underwriters' Laboratories (UL). All broadcasting/receiving components and system shall be approved by the Federal Communications Commission (FCC).

Add to paragraph 2.1:

SUGGESTED SUPPLIERS:

- 1. www.centrumsound.com -408-736-6500
- 2. www.audiogear.com – 800-959-4252

Add to paragraph 2.2 D2:

Chargers: Williams Sound #AT534 (2-Unit Charger).

11. ITEM NO. PM-11

Reference: Section 16760 Digital Video Surveillance System

Description: Replace entire section with attached, including

Attachment: Section 16760 Digital Video Surveillance System (Addendum 1)

DRAWINGS

1. Item No. DWG-1

Reference: Sheet G0.00 COVER SHEET / DRAWING INDEX

Description: ADD: C2.1 DEMO PLAN

DELETE: FA-0.01 FIRE ALARM BUILDING A&B COVER SHEET

REVISE: HZ0.0 to read HZ0.1 TITLE SHEET

2. Item No. DWG-2

Reference: Sheet A2.00A BUILDING A BASEMENT LEVEL DEMOLITION PLAN

Sheet A2.01A BUILDING A GROUND LEVEL DEMOLITION PLAN

Sheet A2.02A BUILDING A SECOND FLOOR DEMOLITION PLAN

Description: CLARIFY demolition plans to indicate wall demo and put-back for all new plumbing to be included. Typical of all classrooms.

Attachments: SK-1 Boys' Room 002

SK-2 Classrooms – Demo

SK-3 Classrooms - New

3. Item No. DWG-3

Reference: Sheet A2.01B BUILDING A GROUND LEVEL FLOOR PLAN

Sheet A5.06 BUILDING A ENLARGED CLASSROOM 104 (105 SIM)

PLANS & ELEVATIONS

Sheet A5.07 BUILDING A ENLARGED CLASSROOM 106

PLANS&ELEVATIONS

Description: New or revised cabinetry to add counter sinks with bubblers at each (3) Kindergarten Classroom.

Attachments: SK-4 Kindergarten Classrooms 104 + 105

SK-5 Kindergarten Classrooms 106

4. Item No. DWG-4

Reference: Sheet A9.03 details 8, 9, 10, 11

Description: All counter elevation dimensions in all Classrooms to conform to the accessible dimensions for grades K-5 per Sheet A10.01: 31" maximum and 24" minimum above finish floor.

5. Item No. DWG-5

Reference: Sheet A1.02 MODERNIZATION SITE PLAN

Description: Revise note at Gas Meter as follows:

INSTALL (N) ~~CHAIN LINK FENCE~~ / **PREFABRICATED** ENCLOSURE
AS INDICATED **AND SPECIFIED**. PATCH AND FILL ALL EXISTING
NON-UTILIZED HOLES FROM REMOVED FENCING.

6. Item No. DWG-6

Reference: Sheet E4.00, detail 5
Description: Replace the Security System Riser Diagram
Attachment: SK-6

7. Item No. DWG-7

Reference: Sheet E5.02, detail 5
Description: Replace the Security Camera and Motion Sensor Schedules
Attachment: SK-7

ATTACHMENTS:

Project Manual:

Section 00400 Bid Form
Section 00480 Project Labor Agreement – Letter of Assent
Section 16720 Motion Detection Security System
Section 16760 Digital Video Surveillance System

Sketches:

SK-1 Boys' Room 002
SK-2 Classrooms – Demo
SK-3 Classrooms - New
SK-4 Kindergarten Classrooms 104 + 105
SK-5 Kindergarten Classrooms 106
SK-6 Security System Riser Diagram
SK-7 Security Camera and Motion Sensor Schedules

END OF ADDENDUM ITEMS